

Red Line 5 Channel - Scalloped Lid






Heavy duty 5 channel with Dog-bone connectors for use with high volume vehicular traffic. Highly visible with red extra thick lids, black base and low angle (20°) black side ramps.



Maximum load per axle 9140 Kg @ 20°C.

Notes: Red Line 5 Channel - Scalloped Lid (RL5-33-SL) also connects directly to a RL5-31-LW

Model	No. of Channels	Channel Size W × H (mm)	Height (mm)	Width (mm)	Length (mm)	Weight (kg)
RL5-33-SL	5	(4 ×) 33 × 35 (1 ×) 39 × 35	46	505	910	11.6



Increased channel height ideal for larger cable diameters